

5.4 Abutment 4: Bank Seat on Reinforced Soil

5.4.1 Description

Abutment 4 is bank seat abutment on reinforced soil.

The fill is compacted in suitable layers and is reinforced using Geogrid mats laid at regular height intervals (typically 600mm) through the abutment. The reinforced soil is founded on a piled reinforced concrete base. Construction works take place behind the concrete facing panels. Back of wall drainage is installed as the backfilling progresses behind the abutments.

Refer to drawing 4300392/1700/107 in Appendix A.

5.4.2 Estimated initial budget works estimate of carrying out the works

See Appendix B.

5.4.3 Whole life costs

Whole Life Costs have been calculated over a period of 120 years. See Appendix B.

5.4.4 Key risks

None.

5.4.5 Assumptions

None.

5.4.6 Departures from standards

None.

5.4.7 Benefits and Dis-benefits

Benefits

- Bank seat abutments are simple to construct.
- Reinforced earth construction can be done in conjunction with the embankment construction.

Dis-benefits

 Piled foundations are still required therefore the cost saving advantages of reinforced soil are not as great as would otherwise be the case.



6 Discussion

6.1 Construction

6.1.1 Construction Traffic Management

Access to the structure will be through the KCC infrastructure from the south or through the developer construction to the north. Pedestrian of vehicular access to the site shall be prohibited during the construction of the viaduct.

6.1.2 Anticipated Construction Sequence

Note: the sequence will be staged along the length of the bridge therefore items listed below with be run congruently to save time. The following anticipated construction sequence is for a composite deck option.

Set up site compound including welfare facilities, fence off site, excavate to base of pile cap elevation, pile foundations, cast pile cap, cast abutment/columns, backfill as necessary, cast capping beams, install bearings and temporarily fix guided/free bearings, assemble pre-fabricated steel girders with permanent and temporary formwork for deck casting, lift beams into position starting with pier section then abutment/span sections, bolt together girder sections, once girders are connect directly to the permanent fixed bearing the temporary fixings can be released, cast the deck and coping in segments, install parapets, remove temporary formwork, lay carriageway and footway surfacing with provisional ducts for future services, finishing works and demobilisation.

6.2 Maintenance requirements

Two types of steel were considered weathering steel and painted carbon steel. Weathering steel removes the maintenance requirement of the protective coating associated with painted steel. The precast concrete beams also have a relatively lower maintenance requirement as they are not subject to direct corrosion although they are subject to chloride ion attack (from road salt) and carbonation (from the air). They are prepared to a high quality in controlled factory conditions when compared to in-situ concrete, although this benefit is negated by the manufacturers claiming reduced cover allowances. The presence of a joint between the beams at each pier is a potential maintenance liability from chloride ion ingress and carbonation should the deck slab allow water to seep through.



There are two long term principal inspection options available to the scheme. One is to inspect the structure using an overbridge unit, the other is to construct a maintenance access track.

Inspection from the topside would require hire of a MOOG 230 overbridge unit for up to three nights and require two lanes to be closed and traffic lights system in place using the bus lane to allow vehicle movements, alternatively the cycle/footway and one carriageway lane closure with traffic lights in the remaining lane if the no bus lane layout is chosen.

During construction the contractor will have to design and construct an access route. This track and two associated bridges would remain as a permanent maintenance access route for future inspection/maintenance works. It is suggested that this route might be a 3.5m wide grass-crete track or similar permeable construction for flood resilience, and that the bridges be constructed as pseudo-slabs using pre-stressed inverted "T" beams to reduce maintenance.

Consultation with KCC structures management team has highlighted concerns with the use of the permanent maintenance access route. Primarily approval from the Environmental Agency is not anticipated to be granted for this option. In addition KCC would prefer not have liability for the future inspection and maintenance of the access bridges due to their infrequent use.

Both bridge inspection options for of the span over the railway will require a line possession.

The abutments and bearings will be inspectable via a viewing platform, accessible from the footway, or from the inspection gallery (Abutments 2 and 3).

The cable stayed option will required additional inspection/maintenance requirements. The cables prevent an overbridge unit from deploying from the topside therefore and underbridge unit will be required. In addition the pillars and cable ends will need to be inspection via and internal chamber accessible for an internal stairwell, ladder shaft.

Document Title

Structures Options Report



6.3 Environmental considerations

The Sturry Link road does not pass through an Area of Outstanding Natural Beauty, SSSI, National Park or other protected area. The scheme will involve permanent land take from private land owners. The land take within the flood plain for each option is similar, therefore the duration of the project is the significant environmental consideration. The environmental aspects and impacts of this will be detailed in a separate environmental report.

6.3.1 Contamination

The scheme crosses the Great Stour River and part of its flood plain used for flood storage. Therefore temporary effects, including spills and leakages from materials and construction plant and emissions to air, water or land must be eliminated or minimised in method statements for all work elements. All waste should be segregated appropriately and stored in a safe manner. Sub-contractors removing waste from site must possess a current waste carriers license and all waste processing or disposal sites must also be appropriately licensed.

6.3.2 Invasive Species

The Preliminary Ecological Appraisal, report no. Co04300299/EC01 dated July 2015 states:

"No non-native invasive or other notable plants were recorded during the walkover, although Bioscan have noted the presence of the county-rare tufted sedge (Carex elata) in wet pasture north of the river. The invasive Nuttall's waterweed (Elodea Nuttallii) has been recorded by the Environment Agency at Vauxhall Bridge".

6.3.3 Noise

The site lies within a rural landscape that includes industrial buildings. The bridge spans the Ashford to Tonbridge railway. Noisy methods of construction will be avoided where possible and temporary noise attenuation barriers can be utilised if required. Agreed working hours will be strictly followed and advanced notices of work will be issued to local businesses and residents. It is likely that night time works will take place for short periods during construction of the bridge

Project Name Stur

Sturry Link

Document Title

Structures Options Report



6.3.4 Heritage

There are no archaeological or cultural heritage considerations to take into account during the design or construction of the bridge or the associated approach retaining walls.

6.3.5 Air Quality

The local air quality may be affected by dust generated by the works. To control airborne dust generated during the construction works, it is recommended that physical barriers are installed and regular water sprays are carried out to damp dust down, particularly during dry weather periods.

6.3.6 Waste Management

Although no longer a legal requirement by the UK government, due to the scheme's size it would be considered good practice to have a Site Waste Management Plan (SWMP) in place on site. This would help to encourage better waste management practices, reduce the cost of waste disposal and improve environmental performance of the scheme.

Much of the site waste generated from the works will be removed from site and taken to a licensed recycling centre in accordance with the SWMP.

6.3.7 Road Users

No vehicle traffic will be permissible during the construction of the viaduct.



6.4 Combined Budget Works Estimates and Whole Life Costs

The costs given are given in the format (Option).(Width) as appropriate based on the descriptions given in Section 4.

The estimated costs for the bridge deck options with bus lane are shown in Table 1, without bus lane in Table 2, comparable abutment costs in Table 3 and comparable steel option cost in Table 4 below.

 Table 1
 Comparable Cost estimates for options with bus lane

	Capital Cost	Maintenance Cost	Total WLC
Option 1.1 5 No. precast concrete beam	£19,552,957	£349,640	£19,902,597
Option 2.1 4 No. steel beam composite, flat soffit	£21,445,591	£349,640	£21,795,231
Option 3.1 4 No. steel beam composite, curved soffit	£21,667,070	£349,640	£22,016,710
Option 4.1 6 No. steel beam composite, curved soffit	£23,217,419	£349,640	£23,567,059
Option 6.1 Twin tower cable stayed	£23,547,849	£398,776	£23,946,625

 Table 2
 Comparable Cost estimates for options without bus lane

	Capital Cost	Maintenance Cost	Total WLC
Option 1.2 4 No. precast concrete beam	£17,539,516	£229,191	£17,768,707
Option 5.2 Ladder beam composite, curved soffit	£17,901,935	£248,428	£18,150,363
Option 6.2 Twin tower cable stayed	£20,225,672	£299,032	£20,524,704

Table 3 Comparable Cost of abutment options

	Capital Cost	Maintenance Cost	Total WLC
Abutment 1 – Baseline Wing walls perpendicular to abutment face	-	-	4
Abutment 2 Splayed wing walls with inspection gallery	£103,125	£31,560	£134,685
Abutment 3 Splayed wing walls with inspection gallery	£65,625	£14,310	£79,935
Abutment 4 Bank seat on reinforced soil	-£183,750	£43,625	-£140,125



Table 4 Comparable Cost steel options

	Capital Cost	Maintenance Cost	Total WLC
Beam 1 – Baseline Unpainted weathering steel (Corten)	-	-	-
Beam 2 Painted carbon steel	£42,200	£229,954	£272,154

It has been shown that the precast concrete beam options have the lowest estimated capital cost and estimated WLC, both with and without bus lane. The flat and curved steel options are not too dissimilar in cost and are the midrange priced options. The six beam and cable-stayed options are the most expensive. In addition the cable stayed option has approximately £50,000 more maintenance cost compared to the concrete and other steel options. The maximum variance in cost is between the options is 20% therefore n

Abutment options 2 and 3 have increased capital and maintenance costs therefore would not benefit the client. However the capital cost savings for abutment option 4 is beneficial. Therefore this would be the recommended abutment option.

The painted carbon steel has been shown to have very little capital cost compared to the weathering steel. However the cost associated with repainting every 20 years makes a difference on the maintenance cost. The painting schedule would also require specialist measures for paining over the two arms of the Great Stour River and railway. Therefore wreathing steel is recommended for the steel beam options.

6.5 Option Scoring

Each option has been compared on a weighted scoring matrix that consists of three criteria, each criterion having five aspects. The three criteria are Construction, Maintenance and Aesthetics/Environmental.

Construction is broken down into construction cost, weighted 35% and construction hazards, being sub divided into foundations, sub-structure, super structure and erection, weighted 15%.

Maintenance is broken down into maintenance cost, weighted 15% and maintenance hazards, being sub divided into bearings, sub-structure, super structure and joints, weighted 15%.

Project Name

Sturry Link

Document Title

Structures Options Report



Environmental is broken down into aesthetics, weighted 10% and environmental impact, being sub divided into noise/vibration, pollution/ecology, embedded energy and duration, weighted 10%.

Each aspect has been scored between 0 and 10. The cost/aesthetic aspects are scored on a benefit system, scoring 0 for least beneficial and 10 for most beneficial. The twelve hazard/impact aspects are scored on a risk system, scoring 0 for no risk and 10 for maximum risk. The average risk score is then converted to a benefit score prior to weighting.

The options comparison matrices are given in Appendix C.

After review of the scoring matrices Option 3.1 curved soffit steel beam composite and Option 5.2 curved soffit ladder beam composite score best for the with bus lane and without bus lane viaduct respectively.

Document Title

Structures Options Report



7 Conclusions

Amey have been commissioned by Kent County Council (KCC) to develop the concept design of a new link road in the Borough of Canterbury, Kent, to link the A28 Sturry Road to the A291 Herne Bay Road. The scheme involves constructing a new link road spanning two arms of the Stour River and a railway line in order to serve the intended development scheme to the west of Sturry.

Six viaduct options, four abutment options and two types of steel options have been considered and compared in this report. The recommendations for the Sturry Link viaduct are as follows:

4 No. weathering-steel beam composite, curved soffit, on reinforced soil abutments if bus lane is required.

Or;

Weathering-steel ladder-beam deck, curved soffit, on reinforced soil abutments if no bus-lane is required.

All the options have been assessed on the minimum number of spans required, however up to two additional spans to the south can be added dependent upon flood storage requirements.

Document Title Structures Options Report



Appendix A Structures Options Drawings

Document Title Structures Options Report



Appendix B Estimated Costs

Document Title Structures Options Report





Appendix C Options Scoring


Document Title Structures Options Report





Appendix D Network Rail Front End Pack




















WING WALL ALTERNATIVE - OPTION 1 (ISOLATED WING WALLS ON PAD FOUNDATIONS AT 45° SPLAY)



REINFORCED SOIL ABUTMENT



ALTERNATIVE ABUTMENT SECTION - 1



ALTERNATIVE ABUTMENT SECTION - 2

ALTERNATIVE ABUTMENT SECTIONS



(The following information has been collected from Prec Information and Arney Process PLC-H&S-201 – Hazard

This drawing forms a part of the options report for this scheme, and is intended to allow comparison with alternative proposals contained within the options report only. Not for construction.

All measurements are in millimetres unless otherwise stated.
All measurements are in millimetres unless otherwise stated.
All levids are in metres A.S.D. (Above Site Datum),
Do not scale from this drawing, Lies written dimensions only,
The scheme design of the foundations is based upon our interpretation
genetachnical data obtained from 'A28 Sturry Papsas, Geotechnical Site
Investigation, Factual Report Volume II, September 1996' which is

geotechnical data obtained from "A28 Stury Bysess, Contachnical Star investigation, Feature Report Volume 1, Spetimber 1996" which is to full and relevant site investigation. For all design wit be subject to full and relevant site investigation. Constraints to be complied with:

a. No periodiumn to be within 8,0m of top of river bank
b. No pieriodiumn poemitted within the river chained of the constraints of the complied with:
a. No periodiumn poemitted within the river chained of the constraints of the complied of the constraints of the constraints of the constraints of the section of the constraints of the constr

BS DN 1991-2;2003. Allowance made for Special Vet I. Reinforcement quantities for costing purposes only: a. Abutment stems 140 kg/m³ b. Abutment pilec caps 130 kg/m³ c. Abutment piles 120 kg/m³ e. Wing well bases 130 kg/m³ e. Wing well bases 130 kg/m³ e. Wing well bases 130 kg/m³ e. Wing well bases 120 kg/m³ 1. Wing well piles 120 kg/m³ 1. Wing well piles 120 kg/m³ 1. Preliminary sub sot classification considered to be as

Design Sulphate Class DS-1.
 Aggressive Chemical Environment for Concrete - ACEC ClassAC-1s in accordance with BRE Special Digest 1 (BRE 2005).

Rev Chkd Appd Date









A28 STURRY LINK ROAD

STRUCTURES

ALTERNATIVE OPTION DETAILS						
Original Drawing Size: A1						
Scale: As Shown	Copyright © Amey					

4300392/1700/107

Rev P0

Total Project Cost Summary

Ref	Cost Element	Option 1.1	Option 1.2	Option 2.1	Option 3.1	Option 4.1	Option 5.2	Option 6.1	Option 6.2
		ter warming a second					Ladder Deck, 6 Spans,		Twin Tower Cable-
1 1		The second of the second secon	5 Pre-Stressed Beams, 6	4 Girder, 6 Spans, Flat	4 Girder, 6 Spans,	6 Girder, 6 Spans,	Curved Soffit (No bus	Twin Tower Cable-	Stayed, 5 Spans (no Bus
		Spans	Spans (no Bus Lane)	Soffit	Curved Soffit	Curved Soffit	lane)	Stayed, 5 Spans	Lane)
1	TOTAL CONSTRUCTION COST	£7,725,000	£6,475,000	£8,900,000	£9,037,500	£10,000,000	£6,700,000	£10,050,000	£7,987,500
1 1									
2	Developing Business Case	£210,000	£210,000	£210,000	£210,000	£210,000	£210,000	£210,000	£210,000
3	Outline Design	£350,000	£350,000	£350,000	£350,000	£350,000	£350,000	£350,000	£350,000
4	Planning & Consultation Costs	£720,000	£720,000	£720,000	£720,000	£720,000	£720,000	£720,000	£720,000
5	Detailed Design Fees	£540,750	£453,250	£623,000	£632,625	£700,000	£469,000	£703,500	£559,125
6	Supervision Fees	£720,000	£720,000	£720,000	£720,000	£720,000	£720,000	£800,000	£800,000
7	Surveys & Studies	£60,000	£60,000	£60,000	£60,000	£60,000	£60,000	£60,000	£60,000
8	Archaeology Studies	£20,000	£20,000	£20,000	£20,000	£20,000	£20,000	£20,000	£20,000
9	Ecology Studies	£35,000	£35,000	£35,000	£35,000	£35,000	£35,000	£35,000	£35,000
10	Demolitions	£20,000	£20,000	£20,000	£20,000	£20,000	£20,000	£20,000	£20,000
11	Advance Works	£25,000	£25,000	£25,000	£25,000	£25,000	£25,000	£25,000	£25,000
12	Utilities	£135,000	£135,000	£135,000	£135,000	£135,000	£135,000	£135,000	£135,000
13	Accommodation Works	£40,000	£40,000	£40,000	£40,000	£40,000	£40,000	£40,000	£40,000
14	Highway Landscape Manitenance	£0	£0	£0	£0	£0	£0	£0	£0
15	KCC Direct Costs	£324,000	£324,000	£324,000	£324,000	£324,000	£324,000	£396,000	£396,000
16	KCC Legal Costs	£55,000	£55,000	£55,000	£55,000	£55,000	£55,000	£55,000	£55,000
17	KCC Clerk of Works	£63,000	£63,000	£63,000	£63,000	£63,000	£63,000	£77,000	£77,000
18	Land Costs	£1,200,000	£1,200,000	£1,200,000	£1,200,000	£1,200,000	£1,200,000	£1,200,000	£1,200,000
19	Land Disposal	£0	£0	£0	£0	£0	£0	£O	£0
20	LCA Part 1 Costs	£250,000	£250,000	£250,000	£250,000	£250,000	£250,000	£250,000	£250,000
21	Lane Rental	£0	£0	£0	£0	£0	£0	£O	£0
22	Commuted Sums	£1,000,000	£1,000,000	£1,000,000	£1,000,000	£1,000,000	£1,000,000	£1,000,000	£1,000,000
23	KCC Adoption Fees	£0	£0	£0	£0	£0	£0	£0	£0
24	Funder Monitoring	£10,000	£10,000	£10,000	£10,000	£10,000	£10,000	£10,000	£10,000
25	Network Rail					The state of the s	100010400000		
26	Possessions	£250,000	£250,000	£250,000	£250,000	£250,000	£250,000	£250,000	£250,000
27	Design Supervision	£475,000	£475,000	£475,000	£475,000	£475,000	£475,000	£475,000	£475,000
28	TOC Compensation	£25,000	£25,000	£25,000	£25,000	£25,000	£25,000	£25,000	£25,000
29	Track Monitoring	£100,000	£100,000	£100,000	£100,000	£100,000	£100,000	£100,000	£100,000
30	Sundry Costs (Advertising etc)	£50,000	£50,000	£50,000	£50,000	£50,000	£50,000	£50,000	£50,000
31	Risks	£3,283,188	£2,948,813	£3,597,500	£3,634,281	£3,891,750	£3,009,000	£3,946,625	£3,394,906
32	Sub-Total	£17,685,938	£16,014,063	£19,257,500	£19,441,406	£20,728,750	£16,315,000	£21,003,125	£18,244,531
	545 1544		,,		,		,,		
33	Inflation (4Q 2016 - 1Q 2019)	£1,867,019	£1,525,454	£2,188,091	£2,225,664	£2,488,669	£1,586,935	£2,544,724	£1,981,141
34	TOTAL ESTIMATED PROJECT COST (excluding VAT)	£19,552,957	£17,539,516	£21,445,591	£21,667,070	£23,217,419	£17,901,935	£23,547,849	£20,225,672
35	TOTAL WHOLE LIFE COST (excluding VAT)	£349,640	£229,191	£349,640	£349,640	£349,640	£248,428	£398,776	£299,032
36	TOTAL COMBINED COST (excluding VAT)	£19,902,597	£17,768,707	£21,795,231	£22,016,710	£23,567,059	£18,150,363	£23,946,625	£20,524,704
\vdash									

STURRY LINK ROAD BRIDGE OPTIONS COST PLAN No 1 - 10th February 2017

Elemental Construction Costs

	nental Construction Costs	Option 1.2 Option 2.1								Option 3.1				Ontion 4.1		Option 5.2									
		9	Pre-Stre	Option 1.1 essed Beams,	6 Spans	4 Pre-St	e-Stressed Beams, 6 Spans (no Bus Lane) 4				4 Gird	ler, 6 Spans, Fla	4	r, 6 Spans, Curv	ed Soffit		6 Girde	Option 4.1 er, 6 Spans, Cur	ved Soffit	Ladde	Soffit (No bus				
Item	n Description	Quantity	Unit	Rate	£	Quantity	Unit	Rate	£	Quantity	Unit	Rate	£	Quantity	Unit	Rate	£	Quantit	y Unit	Rate	£	Quantity	Unit	lane) Rate	£
	Series 200: Site Clearance																								
Α	General allowance for site clearance	5,600	m2	0.50	2,800.00	5,600	m2	0.50	2,800.00	5,600	m2	0.50	2,800.00	5,600	m2	0.50	2,800.00	5,600	m2	0.50	2,800.00	5,600	m2	0.50	2,800.00
	Series 200: Site Clearance				2,800.00				2,800.00				2,800.00				2,800.00		_	1	2,800.00				2,800.00
	Series 300: Fencing																								
Α	Knee Rails	0	m	25.00	0.00	0	m	25.00	0.00	0	m	25.00	0.00	0	m	25.00	0.00	0	m	25.00	0.00	0	m	25.00	0.00
В	,	0	m	320.00	0.00	0	m	320.00	0.00	0	m	320.00	0.00	0	m	320.00	0.00	0	m	320.00	0.00	0	m	320.00	0.00
С	General Site Fencing	0	m	29.40	0.00	0	m	29.40	0.00	0	m	29.40	0.00	0	m	29.40	0.00	0	m	29.40	0.00	0	m	29.40	0.00
	Series 300: Fencing				0.00				0.00				0.00				0.00		_	T	0.00				0.00
	Series 400: Safety Barriers																								
А	Vehicle Parapet; metal parapet system N2/W2 with mesh infil, 1m high	239	m	500.00	119,500.00	239	m	500.00	119,500.00	239	m	500.00	119,500.00	239	m	500.00	119,500.00	239	m	500.00	119,500.00	239	m	500.00	119,500.00
В	Pedestrian Parapet; metal parapet system N2/W2 with mesh infil, 1.4m high	239	m	600.00	143,400.00	239	m	600.00	143,400.00	239	m	600.00	143,400.00	239	m	600.00	143,400.00	239	m	600.00	143,400.00	239	m	600.00	143,400.00
	Series 400: Safety Barriers				262,900.00				262,900.00				262,900.00				262,900.00				262,900.00				262,900.00
	Series 500: Drainage																								
	Surface Water Drainage																								
Α	Rod access points to Beaney kerb (2no/25m)	44	nr	325.00	14,404.00	44	nr	325.00	14,404.00	44	nr	325.00	14,404.00	44	nr	325.00	14,404.00	44	nr	325.00	14,404.00	44	nr	325.00	14,404.00
В	Allowance for connection to existing highway drainage services		item		5,000.00		item		5,000.00		item		5,000.00		item		5,000.00		item	i	5,000.00		item		5,000.00
	Series 500: Drainage				19,404.00				19,404.00				19,404.00				19,404.00			1	19,404.00			19,404.00	
	Series 600: Earthworks																								
Α	Excavate class 5a (topsoil) and deposit on site.	0	m3	8.00	0.00	0	m3	8.00	0.00	0	m3	8.00	0.00	0	m3	8.00	0.00	0	m3	8.00	0.00	0	m3	8.00	0.00
В	Excavate Class 5a (topsoil) and dispose off-site.	195	m3	25.00	4,880.00	195	m3	25.00	4,880.00	101	m3	25.00	2,515.00	101	m3	25.00	2,515.00	101	m3	25.00	2,515.00	86	m3	25.00	2,145.00
С	Excavate acceptable material and deposit on site	0	m3	8.00	0.00	0	m3	8.00	0.00	0	m3	8.00	0.00	0	m3	8.00	0.00	0	m3	8.00	0.00	0	m3	8.00	0.00
D		4,034	m3	24.00	96,816.00	3,967	m3	24.00	95,198.40	3,671	m3	24.00	88,104.00		m3	24.00	91,296.00					3,969	m3	24.00	95,256.00
E		211	m3	69.00	14,590.74	208	m3	69.00	14,358.21	377	m3	69.00	26,024.04	195	m3	69.00	13,470.87	208	m3	0.500(1.50	1300	203	m3	69.00	13,989.06
F		195	m3	37.00	7,222.40	195	m3	37.00	7,222.40	101	m3	37.00	3,722.20	101	m3	37.00	3,722.20	101	m3	37.00	3,722.20	86	m3	37.00	3,174.60
G	Excavate material in areas of soft fill, remove from site and backfill will acceptable material 50% reclaimed and 50% imported.	0	m3	65.00	0.00	0	m3	65.00	0.00	0	m3	65.00	0.00	0	m3	65.00	0.00	0	m3	65.00	0.00	0	m3	65.00	0.00
н	Extra over for hard dig	0	m3	34.00	0.00	0	m3	34.00	0.00	0	m3	34.00	0.00	0	m3	34.00	0.00	0	m3		0.00	0	m3	34.00	0.00
1		0	m3	72.00	0.00	0	m3	72.00	0.00	0	m3	72.00	0.00	0	m3	72.00	0.00	0	m3			0	m3	72.00	0.00
J		0	m3	27.00	0.00	0	m3	27.00	0.00	0	m3	27.00	0.00	0	m3	27.00	0.00	0	m3		0.00	0	m3	27.00	0.00
К	Allowance for Geotextiles	945	m2	5.00	4,725.80	945	m2	5.00	4,725.80	945	m2	5.00	4,725.80	945	m2	5.00	4,725.80	945	m2		4,725.80	945	m2	5.00	4,725.80
	Series 600: Earthworks				128,234.94				126,384.81				125,091.04				115,729.87				122,510.02				119,290.46

AR/DA/KCC31/170321C1 (Options Report)