



B.3 DA03 Palmarsh and Pennypot

| Folkestone and Hythe Stage 1 SWMP : Summary and Actions Drainage Area 03 | | | |
|--|---|--|---|
| Area overview | | | |
| Area (km²) | 6.7 | | |
| Drainage assets/systems | Туре | Known Issues/problems | Responsibility |
| Drainage assets/systems | Туре | Kilowii issues/problems | nesponsibility |
| Royal Military Canal | Main River | There are issues at Botolph's Bridge and Pennypot, where the canal has overtopped during extreme events. | Environment Agency |
| Drains | Ordinary Watercourse | No known problems along drains | Kent County Council |
| Sewer network | Sewers (combined, foul and surface water) | Known problems of surcharging at locations across the drainage area. | Southern Water |
| Flood risk | | | |
| Receptor | Source | Pathway | Historic Evidence |
| A: Heron's Way, Palmarsh | Overloaded pumping station, unknown whether this was due to pump failure or heavy rainfall | Southern Water sewers | There is historic evidence of flooding from Southern Water due to overloaded pumping station. |
| B. Palmarsh Avenue, Palmarsh | Heavy rainfall resulting in overloaded sewers | Southern Water sewers | There is historic evidence of flooding from Southern Water due to overloaded sewers. |
| C: Shepherds Walk/Romney Way, Pennypot | Heavy rainfall resulting in overtopping of canal banks | Overtopping of canal banks, resulting in localised pathways along Shepherds Walk and Romney Way | There is history of flooding in this area due to fluvial flooding. |





